

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-009-03298-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barton SEC. 12 TWP. 16 RGE. 12W E/W
 Location as in quarters or footage from lines:
C. S. 1/2 NW NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Phillips Petroleum Company
 Lease Name Woydziak #3 Well No. _____
 Office Address Box 287 Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 8-11-82
 Plugging completed 8-17-82
 Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom _____ T.D. 3322

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	766.81	none
				5-1/2"	3317'	677'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Ran 2-3/8" Tubing to 2960', pumped 47 barrels of 9 lb. mud, 50 sacks 50/50 pos,
 4% gel, 3% cc and displaced with 40 barrels of 9 lb. mud. Shot casing @1998', 1804',
 1606', 1416', 1227', 998' 885' and 780'. Pulled a total of 21 joints of 5-1/2"
 casing. Plugged well with 4 sacks hulls, 12 sacks gel, 70 sacks 50/50 pos, 4% gel,
 3% cc, 3 sacks gel, 1 sack hulls, 8-5/8" plug, 80 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
 (Address)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 19 1982 08-19-82
 SUBSCRIBED AND SWORN TO before me this 18th day of August, 1982
 CONSERVATION DIVISION
 Wichita, Kansas

IRENE HOOVER
 State of Kansas
 My Comm. Exp. Aug. 15, 1985

Irene Hoover
 Notary Public.

My Commission expires: _____

Formation Record

Lease **Wojniak**Well No. **3**

FROM	TO	Formation	REMARKS
0	230	Clay and Rock	Elevation - 1863 D.F.
230	410	Shale and Shells	
410	530	Pyrite, Shale and Shells	
530	660	Shale and Shells	
660	707	Pyrite and Red Shale	
707	758	Shale, Shells and Pyrite	
758	764	Anhydrite	
764	780	Red Bed and Shale	
780	1350	Shale and Shells	
1350	1454	Salt, Shale and Shells	
1454	1873	Lime and Shale	
1873	1925	Lime	
1925	2105	Lime and Shale	
2105	2145	Shale and Shells	
2145	2400	Shale	
2400	2720	Lime and Shale	
2720	2783	Lime, Shale and Shells	
2783	3033	Lime and Shale	Top LKC. 3033'
3033	3112	Lime	
3112	3280	Lime and Shale	
3280	3309	Lime	
3309	3322	Shale and Lime	Top Weathered Arbuckle 3316' Top Arbuckle 3317'

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1966

CONSERVATION DIVISION
Wichita, Kansas