

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY McPherson SEC. 8 TWP. 21 RGE. 1 W/E/W
Location as in quarters or footage from lines:
NW/4 SW/4 SE/4

Lease Owner George R. Hess
Lease Name Boesker Well No. #1
Office Address 115 E. Marlin
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 1-20-66
Application for plugging filed 7-1-81
Plugging commenced 7-15-81
Plugging completed 7-24-81
Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Loman
Producing formation _____ Depth to top _____ bottom _____ T.D. 3460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				4 1/2"		1166.10

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plug at 2350' made 15' rock bridge
4 sacks cement. Mudd hole to 165'
15' rock bridge - 2 1/4 yds ready mix.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor H & H Casing Pulling Co.

STATE OF Kansas COUNTY OF Harvey, ss.
Donald A. Hurst (employee or owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Donald A. Hurst
Box 563 Burlington, Ia.
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 81

My Commission expires: 2-10-85



Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1981

CONSERVATION DIVISION
Wichita, Kansas

7-29-81

Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON - KANSAS

67160

January 21, 1966

COMPANY: GEORGE R. HESS
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: Boesker #1
 LOCATION: NW/4 SW/4 SE/4, Sec. 8-21-1W,
 McPherson County, Kansas
 COMMENCED: January 8, 1966
 COMPLETED: January 20, 1966
 ELEVATION: 1504 K.B.

0	to	80	Shale
80	to	90	Sand
90	to	132	Shale
132	to	535	Shale & Lime
535	to	755	Lime
755	to	1115	Lime & Shale
1115	to	2110	Shale & Lime
2110	to	2335	Lime, Shale & Sand
2335	to	2740	Lime
2740	to	2947	Shale & Lime
2947	to	3206	Mississippi
3206	to	3310	Shale
3310	to	3417	Shale & Lime
3417	to	3452	Viola Lime
3452	to	3460	Simpson
		3460	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL - 6 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 12 1/4 in. hole to 132 ft. and run 135 ft. of 8 5/8 in. surface pipe and cemented on bottom at 132 ft. with 90 sacks cement. Plug down at 2:15 P.M., January 8, 1966. Cut 7 7/8 in. hole to 3460 ft. and run 3451 feet of 4 1/2 in. O.D. casing and cemented at 3423 ft. with 125 sacks cement. Plug down at 3:30 P.M., January 20, 1966. DST #1 from 2949 to 3000ft. Open 43 mins. Gas surfaced in 23 mins. and not enough to measure. Pressures were ICIP - 15 mins. 701# and FCIP - 10 mins. 540#. Recovery 100 ft. of non-salty drilling mud. DST #2 from 3335 to 3370ft, Open 1 hour. ICIP - 20 mins. 299lbs. FCIP - 30 mins. 72lbs. Received 15 foot of drilling mud with few specks of oil. * No oil mixed with mud. No oil ahead of cement.

TOPS: Brown Lime - 2264' Kansas City - 2318' Mississippi - 2947'
 Kinderhook - 3232' Hunton - 3340' Viola - 3417' Simpson - 3452'

MEASUREMENTS TAKEN FROM K.B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Boesker #1, located on the NW/4 SW/4 SE/4 of Sec. 8-21-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 21st day of January, 1966.

Ruth McVay
 Ruth McVay - Notary Public

My Commission Expires: December 18, 1969.