

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit,
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County. Sec. 8 Twp. 21S Rge. (X) 1 (W)
Location as "NE/CNW/SW" or footage from lines NW SE SW
Lease Owner Messman-Rinehart Oil Company
Lease Name Chavez Well No. 2
Office Address 1432 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 18, 1965
Application for plugging filed November 18, 1965
Application for plugging approved November 18, 1965
Plugging commenced November 18, 1965
Plugging completed November 18, 1965
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug and 1/4 sack hulls. Placed 25 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/4 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC - 6 1965

CONSERVATION DIVISION
Wichita, Kansas

12-6-65

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 412 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF BUTLER, ss.
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
412 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of November, 1965

My commission expires April 30, 1967

Betty Brandt
Betty Brandt Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Messman-Rinehart Oil Company DRILLING COMMENCED: November 10, 1965
 1432 Wichita Plaza
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: November 18, 1965
 412 Union Center
 Wichita, Kansas

CASING RECORD: 10 Jts. 210' 8-5/8" LOCATION: Chavez No. 2
 cemented with 150 sacks NW SE SW
 Section 8-21S-1W
 McPherson County, Kansas

0 - 209 Shale & lime
 209 - 350 Shale
 350 - 650 Lime & shale
 650 - 2005 Shale & lime
 2005 - 2220 Lime & shale
 2220 - 2343 Shale & lime
 2343 - 2402 Lime & shale
 2402 - 2665 Lime
 2665 - 2775 Lime & shale
 2775 - 2960 Shale & lime
 2960 - 3030 Lime
 3030 - 3115 Cherty lime
 3115 - 3240 Lime & chert
 3240 - 3282 Lime
 3282 - 3293 Shale & lime
 3293 - 3393 Shale
 3393 - 3412 Dolomite & shale
 3412 - 3420 Shale
 3420 Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 DEC - 6 1965
 REGISTRATION DIVISION
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *Hul Graves*
 President

STATE OF KANSAS)
) SS:
 BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 29th of November, 1965.

My commission expires:
 April 30, 1967

Betty Brandt
 Betty Brandt Notary Public