

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH

			X

Locate well correctly on above  
Section Plat

McPherson County. Sec. 5 Twp. 21 S Rge. 1 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Cherry Drilling Co., Inc.  
Lease Name Wilkening Well No. 1  
Office Address 102 Insurance Bldg. Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-16-57 19  
Application for plugging filed 5-15-57 19  
Application for plugging approved 5-15-57 19  
Plugging commenced 5-16-57 19  
Plugging completed 5-16-57 19  
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3574 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran 1/2 pipe in hole. Layed down same. Ran rest of pipe in hole. Gunned pits. Circ. Went half way to bottom with d. p. Layed it down. Ran rest of d. p. in hole. Gunned pits to raise mud weight. Circ. and brought heavy mud around. Layed down d. p. Filled hole with heavy mud to bottom of surface pipe @ 180'. Built solid rock bridge @ 170'. Displaced 15 sacks of cement through 5 jts. d. p. Top of the bridge @ 25' with 5 sacks cement filling to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Mr. Ruel Durkee  
Address \_\_\_\_\_

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Franklin Hiebert (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Franklin Hiebert  
102 Insurance Bldg. (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 1957

My commission expires Oct. 24, 1960  
Maxine Condon Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas  
5-23-57

PLUGGING  
FILE SEC 5 T 21 1W  
BOOK PAGE 14 LINE 7

CHERRY DRILLING CO., INC.  
102 Insurance Building  
Wichita 2, Kansas

ROTARY DRILLING LOG

Lease: Wilkening

Geologist: W. Pat Simmons  
1801 Porter, Wichita

Well: No. 1

Location: NE NE SE  
Sec. 5-21S-1W  
McPherson Co., Kansas

Surface Pipe: 161.12 $\frac{1}{2}$  Sur. Hole Run 9 Jnts.  
Used 8 5/8" 103.78 overall less threads  
Cemented with 125 sacks cement 2 $\frac{1}{2}$  c. c.

Elevation: 1507 DF  
1505 Gr.

Casing: Dry Hole. Ran 1/2 pipe in hole.  
Layed down same. Ran rest of pipe in  
hole. Gunned pits. Circ. Went half  
way to bottom with D. P. Layed it down.  
Ran rest of d. p. in hole. Gunned pits  
to raise mud weight. Circ. and brought  
heavy mud around. Layed down d. p.  
Filled hole with heavy mud to bottom of  
sur. pipe @ 180' Built solid rock bridge  
@ 170'. Displaced 15 sacks of cement  
through 5 jts. d. p. Top of the bridge  
@ 25' with 5 sacks cement filling to bottom  
of cellar.

Well Commenced: 4-29-57  
Under Surface 4-30-57  
Completed: 5-16-57

Company: Cherry Drilling Co., Inc.  
102 Insurance Bldg.  
Wichita, Kansas

Contractor: Cherry Drilling Co., Inc.

0-420	2630-2955	lime, shale
420-640	2955-3145	lime, chert
640-820	3145-3215	lime
820-950	3215-3455	lime, shale,
950-1055	3455-3470	sand
1055-1575	3470-3490	
1575-1840	3490-3515	sand, lime, shale
1840-2300	3515-3550	shale, sand
2300-2630	3550-3574	

T. D. 3574

GEOLOGIST'S TOPS

Lansing 2945  
Mississippi 2936  
Kinderhook 3256

Maquoketa  
Viola  
Simpson  
Arbuckle

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 23 1957

3359  
3433  
3467  
3549

CONSEALING  
FILE SEC. 5 T. 21 1W.  
BOOK PAGE 4 LINE 7

R. T. D. 3574

The above is a true and correct log to the best of my knowledge.

Subscribed and sworn to before me on this 17th day of May, 1957.

My Commission expires October 24, 1960.

*Maxine Condon*  
Maxine Condon, Notary Public