

5 030354

3-31-88

15.113.19306-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 10-19-37

NE, SEC. 31, T 21 S, R 1 ~~W~~ W

4950 feet from S section line

330 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5663

Lease Name C. Jones Well # 1-A

Operator: Hess Oil Company

County McPherson 106.99

Name &amp; Address P.O. Box 1009

Well Total Depth 3292 feet

Address McPherson, KS 67460

Conductor Pipe: Size feet

Surface Casing: Size 10" feet 162

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Company Tools License Number 5663

Address McPherson, KS

Company to plug at: Hour: AM Day: 28 Month: 3 Year: 19 88

Plugging proposal received from Bryan Hess

(company name) Hess Oil Company (phone)

were: Open hole 3269-92 7" casing @3269' w/300 sxs. Run tubing to approx. 3250'.

Circulate 30 sxs cement. Pull tubing to 250', circulate cement to surface

Run 1 1/2" tubing in between 7" and 10" to 250'. Cement to surface.

Plugging Proposal Received by Merlan Unruh  
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 3:15pm Day: 31 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT Bottom of hole bridged @3208'. Ran tubing 3200' circulated 30 sxs  
cement. Pulled tubing out to 248', circulated cement to surface. Ran 1 1/2"

tubing to 192', could not circulate tubing down hole, apparently on cement.

STATE CORPORATION COMMISSION Circulated cement to surface.

3-30-88--85 sxs 3-31-88--48 sxs

4-11-88

CONSERVATION DIVISION

Remarks: McPherson Concrete Products #3-28-88, 30 sxs

(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 4-13-88

Signed Ralph Tittel - Bottom  
Merlan Unruh - top  
(TECHNICIAN)

INV. NO. 20361

3-31