

6-23

2-070709

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

15.159-06610-0000

API NUMBER: COMP 1961

C SW NW, SECTION 1 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 32081 3300 FEET FROM S SECTION LINE
OPERATOR SMOKEY VALLEY RESOURCES 4620 FEET FROM E SECTION LINE
NAME & RT 3, BOX 63
ADDRESS LYONS, KS 67554

LEASE NAME: LACKEY "B" #3
COUNTY: RICE
WELL TOTAL DEPTH: 3381' 109.88
PIPE: 5 1/2" @ 3378'
SURFACE CASING: 8 5/8" @ 162'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 2:00 DAY: 23 MONTH: 6 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3250' 5 SACKS
35 SACKS AT 750'
35 SACKS AT 550'
275' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: J.L.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 5:00 DAY: 23 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3250' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2220'. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 550', PUMPED 35 SACKS. PULLED TO 275', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #5618

INVOICED RECEIVED
KANSAS CORPORATION COMMISSION

DATE JUL 03 1997 JUL 01 1997
INV. NO. 48492

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI

FORM CP-2/3
REV. 3/90