

4-16

5
2-060247 412
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-159-21,941-0000
C N/2 NE SW, SECTION 1 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 6522 2310 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR Kansas Horizon Oil Co.
NAME & RR #1
ADDRESS Windom, KS 67491

LEASE NAME: Lackey #1

COUNTY: Rice 111.80

WELL TOTAL DEPTH: 3440'

PIPE: 5-1/2" @ 3439'/75 SX

SURFACE CASING: 8-5/8" @ 221'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling, Inc.
ADDRESS: P. O. Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: am DAY: 16 MONTH: 4 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Kelso - Manny
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Sand to 3310' - cap w/5 sx cmt - shoot pipe - pull csq to 850' - 35 sx cmt - pull csq to 350' - circ cmt to surf.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00p DAY: 16 MONTH: 4 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded to 3310' - capped w/5 sx cmt - shot pipe - pulled csq to 852' - loaded w/water - 35 sx cmt - pulled csq to 363' - circ 100 sx cmt to surf - perms: 3369-76', 3381-96', 3394-98' - recovered 2600' of 5-1/2"

REMARKS: Allied Cementing #2765 60/40 poz 2% gel

5-2-91
RECEIVED
CONSERVATION COMMISSION
MAY 2 1991
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE 5-9-91
INV. NO. 31785

R. Phil Worley
R. Phil Worley (AGENT)

DW