

70114

15.159.04257.0000

6-26

2-070711

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-159-04257 00-00  
6W

SE NW NW, SECTION 1 TOWNSHIP 21 RANGE 1W

OPERATOR LICENSE # 32081 4290 FEET FROM S SECTION LINE  
OPERATOR SMOKEY VALLEY RESOURCES 4290 FEET FROM E SECTION LINE  
NAME & 1325 HIGHWAY 56  
ADDRESS LYONS, KS 67554

LEASE NAME: LACKEY "B" #2  
COUNTY: RICE 109.27  
WELL TOTAL DEPTH: 3362'  
PIPE: 5 1/2" @ 3353'  
SURFACE CASING: 8 5/8" @ 140'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: CHASE, KS LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 26 MONTH: 6 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3300' AND 5 SACKS  
35 SACKS AT 750'  
35 SACKS AT 550'  
250' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL  PART  NONE

COMPLETED: HOUR: 1:30 DAY: 26 MONTH: 6 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3300' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2614'. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 550', PUMPED 35 SACKS. PULLED TO 250', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #5620

**INVOICED**

DATE JUL 03 1997

INV. NO. 48491

6-26

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 03 1997

CONSERVATION DIVISION  
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Jack Luthi  
JACK LUTHI

FORM CP-2/3

REV. 3/90