

4-11

2-100704 286

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-159-21, 826-0000

NE SE SE, SECTION 1 TOWNSHIP 21 RANGE 6W

OPERATOR LICENSE # 6522 990 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR Kansas Horizon Oil Co.
NAME & Route #1
ADDRESS Windom, KS 67491

LEASE NAME: Blew #3
COUNTY: Rice

WELL TOTAL DEPTH: 3431' 111.50

CONDUCTOR PIPE: 5-1/2" @ 3436'

SURFACE CASING: 8-5/8" @ 264'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: Perfs 3354-64' 3346-52'

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 1:45 DAY: 11 MONTH: 4 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Millard Kelso
COMPANY NAME: Kelso Casing Pulling PHONE: _____

WERE: Sand 50' above top perf 5 sx - shoot & pull pipe to 360' - spot 50 sx - pull 3 jts pipe to 230' - circ to surface.

PLUGGING PROPOSAL RECEIVED BY: John Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 5:15p DAY: 11 MONTH: 4 YEAR: 1991

ACTUAL PLUGGING REPORT:
Sanded to 3300' & dumped 5 sx cmt w/bailer - shot & pulled 1650' of 5-1/2" to 750' - spotted 35 sx cmt - pulled pipe to 350' - spotted 50 sx cmt - pulled pipe to 230' - circ w/60 sx cmt

REMARKS: Allied #1718 60/40 4% gel

I DID NOT OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION

APR 9 1991

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90

J. L. Sanders
J. L. Sanders (AGENT)

INVOICED

DATE 4-23-91

INV. NO. 31635

DW

4-11