

District Plugging Report

Spot: NENENE

Spot: NENENE Sec 9 Twp 19 S Rng 21 ☒ E / ☐ W

4819 _____ Feet from ☐ N / ☒ S Line of Section

Feet from E / W Line of Section

GPS: Lat: 38.417560 **Long:** 95.086390 **Date:** ~~5/31/17~~ 9/21/16

Lease Name: Regerton-Rohrer **Well #:** Reg 01

County: Franklin Total Vertical Depth: 695 feet

Operator License No: 101

Op Name: STATE OF KANSAS

Address 1: 266 N. Main St. Ste. 266

Address 2:

City: WICHITA

State: KS **Zip Code:** 67202 **Pin:** 1513

Well Type: GAS - Natural Gas - Production

Plug Co License No.: 33749

Proposal Revd from: Mike Kepley

UIC Docket No.:

Plug Co. Name: KEPLEY WELL SERVICE, LLC.

Company Name: KWS.

Date/Time to Plug: ~~3/24/17~~

SERVICE, LLC. 3/23/17

Phone: (620) 431-8945

Proposed Plugging Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle

Witness Type: COMP - Complete 100%

Date/Time Plugging Completed: 3/24/17

KCC Agent: Frank Guilfoyle

Actual Plugging Report: 3/23/17

Perfs:

Top

Bottom

Thru

Dig around well to cut drive pipe and 2" pipe to get to straight pipe. Run 1" outside 2" to 400 ft and hit hard. Run 1" inside 2" to 690 ft. Wash inside 2" to 695 ft. Pump Portland cement to surface inside and outside 2". Pump total of 176 sacks of cement. Well plugged.

Remarks

Control No. ~~20170011-01~~. Contract No. 38595. GPS'ed by TH & FG in NAD 83. Reg Section

20170011-001

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☐ No

District: ~~04~~ 03

Received
KANSAS CORPORATION COMMISSION

JUN 02 2017

CONSERVATION DIVISION
WICHITA, KS

(Technician)

Form: District Plugging Report —