

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-009-21,862 0000
100'E.of
SW SW NW /4 SEC. 13, 16 S, 12 W
2970 feet from S section line
4850 feet from E section line

Operator license# 6357

Lease Weber well # 1

Operator: Webco Oil Company

County Barton 108.45

Address: 1303 Baker
Great Bend, Kansas 67530

Well total depth 3337 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 393 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 8:30A.M. Day: 19 Month: May Year: 95

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 240 sxs. 60/40 posmix - 10% gel and hulls.
Plug while pulling casing.

RECEIVED
STATE CORPORATION COMMISSION
MAY 23 1995
05-23-95
WIC. 13 60687

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:15P.M., Day: 19, Month: May, Year: 95

Actual plugging report: 8 5/8" to 393'. 5 1/2" to 3335'. Sanded to 3280' and
spotted 5 sxs. cement with dump bailer. Shot casing loose at 2000' and
pulled to 1475'. Mixed and pumped 105 sxs. cement with 200# hulls. Pulled
casing to 925' and pumped 30 sxs. cement with 200# hulls. Pulled casing to
450' and circulated cement with 65 sxs. with 100# hulls.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1891 GL

I did[X] / did not[] observe the plugging.

Herb Deines
AK (agent)

INVOICED

DATE JUN 13 1995

INV. NO. 42962