

4-041605

8-23 15-009-03305-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 2-14-46

S2 SE SW /4 SEC. 13, 16 S, 12 W
330 feet from S section line
3300 feet from E section line

Operator license# 6588

Lease Dolechek well # 5

Operator: Woodman - Iannitti

County Barton

Address: P.O. Box 308
Great Bend, Kansas 67530

Well total depth 3338 feet ^{108.49}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 12 1/2 Inch @ 353 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing - D.S. & W. Servicing License#

Address: Russell, Kansas - Claflin, Kansas

Company to plug at: Hour: 9:00A.M. Day: 23 Month: August Year: 94

Plugging proposal received from: Dick Iannitti

Company: Woodman-Iannitti Phone:

Were: 5 1/2" casing set @ 3330' w/100 sxs. cement. O.H. @ 3330' -
3338' Salt @ 1600' - Dakota @ 360'. Hole in casing at 690'.
Ordered 250 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls
plus 8 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:30P.M., Day: 23, Month: August, Year: 94

Actual plugging report: R.I.H. with tubing to 3250'. Spotted 8 sxs.
gel with 50 sxs. cement with 300# hulls. Pulled to 1600' - spotted 75
sxs. cement with 100# hulls - Pulled to 800'. Spotted 50 sxs. to
circulate at surface. Pulled tubing and pumped to circulate 75 sxs.
cement from perms. at 360' to surface. Max. 300#. S.I.P. 400#.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1994

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

CONSERVATION DIVISION
WICHITA KANSAS

I did X did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE SEP 12 1994

INV. NO. 41203