

6 070349

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-009-19350-8001  
NW 1/4, SEC. 18, T 16 S, R 12 W  
330 feet from S & section line  
660 feet from E & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6911  
Operator: Phillips Oil Company  
Name & Address Box 287  
Great Bend, Kans.

Lease Name Kraft-Prusa Well # D-0-1  
(SWD) 121.55  
County Barton  
Well Total Depth 3740 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8" feet 504 ✓

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor (B.J.) SUN OIL WELL CMT. License Number \_\_\_\_\_

Address BOX 169 GREAT BEND, MS. 67530

Company to plug at: Hour: 12:10 PM Day: 9th Month: APRIL Year: 19 85

Plugging proposal received from BILL MILLS

(company name) Phillips Oil Company, Inc. (phone) 316-793-8424

were: 8 5/8" 504 FE SP. CUL 150' ent, 5 1/2" Csg @ 3380 FE CUC 1000' ent.

Temp Survey to (cmt 600 FE) 4 1/2" Liner @ 3355 FE to 3454 FE 1/60' common ent.

Open Hole 3454 FE to 3529 FE, Plug Back T.D 3529 FE, PERFS 3407' 3448'

1180 FE 2 1/8" Fiberglass in Hole, AND 100 FE 2 1/8" DUOLINE TUBING, TRIED TO FISH OUT.

ORDER 500 <sup>50'</sup> /50 POZMIX GEL - CA-CL - CELLULOSE, 5 <sup>50'</sup> HULL'S, AND 5 1/2" PLUG. LOAD BOTH.

ANNULUS AND 5 1/2" Csg / CEMENT Tagging Proposal Received by Marion Schmidt  
DUMP IN WITH PUMP TRUCK. OPIC (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 PM Day: 11th Month: APRIL Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 500 <sup>50'</sup> /50 POZMIX GEL - CA-CL, 2 <sup>50'</sup> FLAME, 5 <sup>50'</sup> HULL'S, 5 1/2" PLUG.

TOOK INJECTION RATE, 50 PSI. NO RETURNS FROM ANNULUS. ANHYDRITE TOP 750 FE.

Pumped in 5 1/2" csg. 150 <sup>50'</sup> ent, 150 <sup>50'</sup> ent 1/2 Cello 1/2 FLAME + 1/4 HULL'S, THEN 50 <sup>50'</sup> ent 1/2 HULL'S.

Released plug AND 150 <sup>50'</sup> ent. (ON VACUUM) Pumped in Annulus 100 <sup>50'</sup> ent 1/2 Cello 1/4 HULL'S

ANNULUS ON (VACUUM). Returned on April 11, <sup>50'</sup> WITH ANOTHER 300 <sup>50'</sup> /50 GEL CA-CL, 2 <sup>50'</sup> FLAME

AND 2 <sup>50'</sup> HULL'S, Pumped in 5 1/2" csg 150 <sup>50'</sup> ent 1/2 Cello AND 2 <sup>50'</sup> HULL'S, MAX. PSI'S 900, SHUT IN 400 PSI'S.

Remarks: Pumped 150 <sup>50'</sup> ent in Annulus 1/2 Cello 1/4 HULL'S, MAX 500 - shut in 400 PSI'S

Cemented B (B.J.) SUN OIL WELL Cementing.

NOTICED (If additional description is necessary, use BACK of this form.)

DATE 4-29-85 APR 22 1985 04-22-85 Signed Marion Schmidt  
OPIC (TECHNICIAN) 32  
4-19-85

INV. NO. 7881 CONSERVATION DIVISION Wichita, Kansas FORM CP-2/3 Rev. 01-84