

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 27 Twp. 21S Rge. (E) 1 (W)

Location as "NE/CNW/SW" or footage from lines Ctr. NE/4 NW/4

Lease Owner Donald C. Slawson

Lease Name La Gree Well No. 1

Office Address 408 One Twenty Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed 11-14 19 63

Application for plugging filed 12- 3 19 63

Application for plugging approved 12- 3 19 63


Plugging commenced 11-26 19 63

Plugging completed 11-26 19 63

Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Cecil Jones, McPherson, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3517 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Water	0	199'	8-5/8"	199'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 190', set plug at 190' with 1/4 sacks of hulls and 20 sacks cement. Filled hole with mud to 40', set plug #2, then filled hole with 1/4 sack hulls and 10 sacks common cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Renfro Drilling Co.

Address 316 Insurance Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl H. Renfro
316 Insurance Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1963

My commission expires February 27, 1965

Henry D. Ficken
Notary Public.



LaGree "H" #1
 Ctr. NE/4 NW/4 Sec. 2/-218-1W,
 McPherson County, Kansas

Date Commenced - November 14, 1963
 Date Completed - November 26, 1963
 Elevation -
 Casing - 199' 8-5/8" new, cemented 175 sx. common.

DRILLERS LOG

- 0 -	199	Shale & Lime
199 -	335	Shale
335 -	580	Shale & Lime
580 -	865	Shale & Lime
865 -	1130	Shale & Lime
1130 -	1450	Lime & Shale
1450 -	1695	Shale & Lime
1695 -	1850	Lime & Shale
1850 -	2025	Lime
2025 -	2165	Lime
2165 -	2330	Lime & Shale
2330 -	2465	Lime & Shale
2465 -	2558	Kansas City
2558 -	2620	Lime
2620 -	2705	Lime
2705 -	2835	Lime & Shale
2835 -	2940	Lime & Shale
2940 -	2950	Lime & Shale
2950 -	3005	Lime & Chert
3005 -	3114	Miss.
3114 -	3153	Miss.
3153 -	3190	Miss. Lime
3190 -	3225	Miss.
3225 -	3325	Lime
3325 -	3381	Lime
3381 -		DST #1 - Misrun
3381 -	3458	Lime & Shale
3458 -	3500	Viola
3500 -	3517	Simpson -DST #2 3492-3517'
3517		Total Depth D & A

RECEIVED
 STATE CORPORATION COMMISSION

DEC 11 1963

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss.
 SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

RENFRO DRILLING COMPANY

By Earl H. Renfro
 Earl H. Renfro

Subscribed and sworn before me this 10 day of December, 1963.

By Henry D. Fickens
 Notary Public

My Commission expires February 27, 1965