


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County. Sec. 27 Twp. 21S Rge. 1 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE
Lease Owner O. A. Sutton
Lease Name Dirksen Well No. 1
Office Address 407 Insurance Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 2-25 1959
Application for plugging filed 2-25 1959
Application for plugging approved 2-25 1959
Plugging commenced 2-25 1959
Plugging completed 2-25 1959
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3528 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	196'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud from 3528 up to 210. Set plug # 1 at 210'. Mixed 1/4 sack hulls and 15 sacks cement.
Filled with mud 165' up to 30'. Set plug @ 30'.
Mixed 1/4 sack hulls and 8 sacks cement. Filled rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1959
CC
VISITOR

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. S. Sutton & Sons
Address 313 Insurance Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
A. L. Rhodes (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]

(Address) _____
SUBSCRIBED AND SWORN to before me this 26th day of February, 1959
My commission expires November 9, 1961
Marilyn E. Fox Notary Public.

PLUGGING
FILE SEC 27 T. 21. R. 1W
BOOK PAGE 11 LINE 11

O. A. Sutton, Dirksen #1
NE NE NE Sec. 27-21S-1W
McPherson County, Kansas

Commenced - February 14, 1959
Completed - February 25, 1959
Casing - 196' of 8-5/8" w/125 sacks cement
Elevation - 1513 KB

DRILLERS LOG

0 - 196	Surface
196 - 420	Shale and lime
420 - 680	Shale and lime
680 - 860	Lime and shale
860 - 1090	Lime
1090 - 1520	Shale
1520 - 1785	Shale and lime
1785 - 1969	Lime and shale
1969 - 2115	Lime and shale
2115 - 2345	Lime and shale
2345 - 2425	Lime
2425 - 2490	Lime
2490 - 2595	Lime
2595 - 2675	Lime
2675 - 2755	Lime
2755 - 2853	Lime
2853 - 2935	Lime and shale
2935 - 2968	Lime and shale
2968 - 2995	Lime
2995 - 3115	Lime
3115 - 3163	Lime
3163 - 3220	Lime
3220 - 3258	Lime
3258 - 3320	Lime and shale
3320 - 3370	Shale and lime
3370 - 3385	Lime
3385 - 3435	Lime and shale
3435 - 3480	Lime
3480 - 3508	Lime
3508 - 3529	Lime and sand
3529 -	Rotary Total Depth
	D & A

RECEIVED
STATE CORPORATION COMMISSION

MAR 3 1959

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I, the undersigned, being duly sworn on oath, state that the above Drillers Log is true and correct to the best of my knowledge and belief and according to the records of this office.

J. S. SUTTON & SONS DRILLING CO.

By Henry D. Dirksen

Subscribed and sworn to before me this 2nd day of March, 1959.

Lorraine Skelton
Notary Public

My commission expires June 1, 1960.

PLUGGING
FILE SEC. 27 T. 21 S. R. 1 W.
BOOK PAGE 19 LINE 11