

STATE OF KANSAS  
ATE CORPORATION COMMISSION  
3 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-04254-00-00  
Comp. 1955

RECEIVED

MAR 21 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Lackey C

WELL NUMBER 1

330 Ft. from N Section Line

3630 Ft. from E Section Line

SEC. 1 TWP. 21 RGE. 6W (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-4-03

Plugging Completed 3-6-03

LEASE OPERATOR Smokey Valley Resources, Inc.

ADDRESS P.O. Box 305 Chase, Kansas 67524

PHONE: (620) 938-2470 OPERATORS LICENSE NO. 32081

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3345'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	140'	None
				5-1/2"	3340'	2320'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3200' and 5 sacks cement. Shot 5-1/2" casing loose @2320' pulled up to 800', pumped 35 sacks cement with 100# hulls, pulled up to 500', pumped 35 sacks cement with 100# hulls, pulled up to 250' and circulated 90 sacks cement to surface. 60/40 pos. 4% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Smokey Valley Resources, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of March, 2003

[Signature]  
Notary Public

My Commission Expires:



[Signature]  
Form 67  
Revised 05-