

STATE OF KANSAS
STATE CORPORATION COMMISSION
301 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-159-35667-00 00
API NUMBER _____
Comp. 1955

RECEIVED

MAR 21 2003

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE NAME Lackey C

WELL NUMBER 2

1650 Ft. from ^N Section Line

3630 Ft. from E. Section Line

SEC. 1 TWP. 21 RGE. 6W (E) or (W)

COUNTY Rice

LEASE OPERATOR Smokey Valley Resources, Inc.

ADDRESS P.O. Box 305 Chase, Kansas 67524

PHONE# (620) 938-2470 OPERATORS LICENSE NO. 32081

Character of Well Oil

Date Well Completed _____

Plugging Commenced 3-3-03

Plugging Completed 3-4-03

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Is plugging proposal was approved on _____ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	145'	None
				5-1/2"	3348'	2300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Plugged off bottom with sand to 2900' and 5 sacks cement. Shot 5-1/2" casing loose @2300', pulled up to 800', pumped 35 sacks cement with 100# hulls, pulled up to 500', pumped 35 sacks cement with 100# hulls, pulled up to 300' and circulated 100 sacks cement to surface, 60/40 pos, 4% gel.
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Smokey Valley Resources, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to be the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of March, 2003

[Signature]
Notary Public

My Commission Expires: _____



Form CP
Revised 05-