

SEP 09 1974

STATE OF KANSAS
STATE CORPORATION COMMISSIONTake All Information Completely
State Corporation Commission
Kans. Div. of Conservation
Conservation Division
State Corporation CommissionP. O. BOX 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Rice County, Sec. 1 Twp. 21 Rge. 6 (E) (W)
 Location as "NE/CN/NE5W4" or footage from lines NW NW NW
 Lease Owner Tomlinson Oil Co., Inc.
 Lease Name Lackey B#1 Well No.
 Office Address Wichita, Kansas 67202
 Character of Well (completed as Oil, Gas or Dry Hole)
 Date well completed 19
 Application for plugging filed 19
 Application for plugging approved 19
 Plugging commenced 8/23/74 19
 Plugging completed 9/3/74 19
 Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
 Producing formation Depth to top Bottom Total Depth of Well 3383 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	150	none
				5 1/2	3355	2318'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3383', ran sand to 3325' and ran 5 sacks cement.
 Loaded hole with water, shot pipe at 2917', 2800', pipe parted.
 Pulled 2318', 70 joints total. Set 10' rock bridge at 210' and
 ran 35 sacks cement. Mudded hole to 40', ran 10 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

OCT 22 1974

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
 Address CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE
 NOEL J. KNIGHT

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

CHASE, KANSAS

Subscribed and sworn to before me this 5th day of Sept. 1974



Margaret Melcher
 Notary Public.

STENOGRAPH

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

15.159-00263-0000


ORIGINAL

AUG 28 1954 Company- STAG DRILLING ET AL
Farm- Lackey "B" No. 1

SEC. 1 T. 21 R. 6W
NW NW NW

Total Depth. 3356'
Comm. 2-28-54
Shot or Treater.
Contractor.
Issued. 8-28-54

County Rice KANSAS



CASING:
8 5/8" 150'
5 1/2" 3356'

Elevation. 1544'

Production. Prop. 25 BQ & trace
wtr.

Figures indicate Bottom of Formations.

soil	150
red rock	240
shale & shells	450
salt	805
lime & shale	1110
sdv lime	1180
lime sdv & shale	1220
lime & shale	1800
shale & shells	2210
lime & shale	2405
lime	2540
shale	2545
lime & shale	2735
lime	3164
lime & shale	3350
Conglomerate	3346
Mississippi	3356
Total Depth	

Tops: Scout	
Kansas City	2749
Conglomerate	3330
Mississippi	3346

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1974
CONSERVATION DIVISION
Wichita, Kansas