


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Rice County. Sec. 1 Twp. 21S Rge. 6W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW  
Lease Owner Stag Drilling, Inc.  
Lease Name Lackey Well No. 1  
Office Address Chase, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed September 14 1954  
Application for plugging filed July 13 1953  
Application for plugging approved July 14 1953  
Plugging commenced July 14 1953  
Plugging completed July 16 1953  
Reason for abandonment of well or producing formation Ceased production



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 1953  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Chat Depth to top 3380' Bottom 3413' Total Depth of Well 3413' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi Chat	Oil & water	3380'	3400'	8-5/8"	150'	None
				5-1/2"	3410'	2931'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole from 3413' to 3399' and ran 6 sacks of cement. Mudded hole from 3350' to 150', set 10' rock bridge to 140' and ran 15 sacks of cement. Mudded hole from 95' to 20' and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
E. E. O'Brien (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. O'Brien

Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of July, 1953

My commission expires May 20, 1957

Edward E. O'Brien Notary Public.

24-7868-S 3-53-20M

**PLUGGING**  
FILE SEC 1 T 21 R 6W  
BOOK PAGE 114 LINE 28

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1953

CONSERVATION DIVISION  
Wichita, Kansas

7-24-53

Contractor's Well Log.

Operator Stag Drilling Inc. Et A Farm Name Lackey Well 1  
 Location NW NW SW Se.1-21S-6W County Rice State Kansas.  
 Commencement Date Sept. 2, 1952 Completion Date Sept. 14, 1952

LOG OF WELL

\* All measurements from top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS.
0	150	Surface soil		
150	495	Shale & Shells		
495	775	Salt	10 - 530'	
775	1125	Lime & Shale	10 - 1000'	
1125	1240	Sandy Lime		
1240	1825	Lime-Shale		
1825	2275	Shale-Shells.		
2275	2400	Lime-Shale.		
2400	2590	Lime		
2590	2759	Sand-Lime-Shale.		
2759	3248	Lime		
3248	3375	Lime-Shale		
3375	3384	Congl.		
3384	3413	Chat		
		TOTAL DEPTH		

Set 150' (8-jts) 8 5/8" Casing.  
 Set 3413' (103 jts) 5 1/2" Casing.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF RICE )

The undersigned certifies that to the best of his knowledge and belief the above facts are true and correct.

STAG DRILLING INC.,  
 BY C. L. Russell  
 PRESIDENT.

Subscribed and sworn to before me this 17th day of September, 1952.

My Commission Expires 3/1/55

Orlando Miller  
 NOTARY PUBLIC

**PLUGGING**  
 FILE SEC 1 T 21 R 6W  
 BOOK PAGE 114 LINE 28

STATE OF KANSAS  
 SEP 24 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas