


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 1 Twp. 21 Rge. 6 (E) (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE
Lease Owner Tomlinson Kathol, Inc.
Lease Name Lackey Estate Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/3/67 _____ 19____
Plugging completed 11/8/67 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3338 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	148'	none
				5-1/2"	3330'	2635'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3320', dumped 5 sacks of cement.
Loaded hole, shot pipe at 2825', worked pipe, shot at 2734' and 2633', worked pipe loose and pulled pipe. Set 10' rock bridge at 210' to 200', dumped 25 sacks of cement. Mudded to 40', 10' rock bridge, capped with 10 sacks of cement. Talled pipe.

PLUGGING COMPLETE.

WICHITA, KANSAS
STATE CORPORATION COMMISSION

NOV 22 1967

11-22-67

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1967

My commission expires NOVEMBER Feb. 15, 1971

Margaret Melcher
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-159-00355-0000


Company- DOZIER OIL COMPANY
Farm- Lackey Estate No. 1

SEC. 1 T. 21 R. 6W
NW NW NE

CORRECTED LOG

Total Depth. 3335
Comm. 5-22-55 Comp. 5-22-55
Shot or Treated.
Contractor. Stag Drilling Co.
Issued. 5-4-57

County Rice
KANSAS



CASING:
8 5/8" 145'
5 1/2" 3332'

Elevation. 1526 R.B.

Production. 25 BO

Figures indicate Bottom of Formations.

surface hole 145
shale, shells 490
salt 760
lime, shale 960
lime sandy, shale 995
lime, shale 1150
lime sandy 1355
lime, shale 1710
shale, shells 2050
lime, shale 2245
lime 2527
shale 2531
lime, shale 2706
lime 3165
lime, shale 3310
Conglomerate 3326
Miss. R.T.D. 3332
lime 3335
Total Depth

Tops:
Brown lime 2706
Lansing 2727
Conglomerate 3310
Mississippi 3326

R.T.D. 3332
CTD 3335

RECEIVED
STATE COMMISSION

NOV 6 1967

CONSERVATION DIVISION
Wichita, Kansas