

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.159-04257-0000

API NUMBER 5-28-54

LEASE NAME Lackey "B"

WELL NUMBER #2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

Ft. from S Section Line

Ft. from E Section Line

SEC. 1 TWP. 21 RGE. 6W (E) or (W)

COUNTY Rice

LEASE OPERATOR Smokey Valley Resources

ADDRESS 1325 Hwy. 56 Lyons, Ks. 67554

PHONE (316) 257-5529 OPERATORS LICENSE NO. #32081

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced 6-23-97

Plugging Completed 6-26-97

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3362

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	140'	none
				5 1/2	3353'	2620

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Sanded bottom to 3300'. Dumped 5 sks. cement. Shot at 2620', pipe came free. Pulled up to 750'. Pumped 35 sks. w/100# hulls. Pulled up to 550', pumped 35 sks. w/100# hulls. Pulled up to 250'. Circulated cement to surface. Pulled rest of casing. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: X Smokey Valley Resources

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 21st day of July, 1997

*Notary Public*  
Notary Public

My Commission Expires:

