


15-009-19335-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barton County, Sec. 11 Twp. 16S Rge. 12 (W)
Location as "NE/CNWSW" or footage from lines NE NE SE
Lease Owner NATIONAL COOPERATIVE REFINERY ASSOCIATION
Lease Name N. J. Weber "A" Well No. 5
Office Address P. O. Box 6, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 8, 19 47
Application for plugging filed March 18, 19 71
Application for plugging approved March 19, 19 71
Plugging commenced April 3, 19 71
Plugging completed April 7, 19 71
Reason for abandonment of well or producing formation Repair of casing leak
was not economically justifiable.
If a producing well is abandoned, date of last production January 3, 19 71
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Arbuckle Depth to top 3329' Bottom 3336' Total Depth of Well 3336' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275'	None
				5 1/2"	3330'	597.40'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.


Ran Howco line and weight to BP @ 610'. Tried to run barrel
but couldn't get past 610'. Ran 2 jts. tbg. and spudded on
BP. Pushed BP to bottom. Dumped 5 sacks cement @ 3275'.
Shot 5 1/2" csg. @ 2490' & 2400'. Pulled 19 jts. casing.
Squeezed well with 3 sacks hulls, 20 sacks gel and 100 sacks
cement. NCRA Representative, Earl Baker. Complete 4-7-71.

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221, Great Bend, Kansas 67530

STATE OF Glenn E. Kansas, COUNTY OF Barton, ss.



Glenn E. Gotsche (employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well and that the same are true and correct. So help me God.

(Signature) I. J. Gotsche District Superintendent

P. O. Box 6, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 20th day of April, 19 71

My commission expires June 3, 1973
Glenn E. Meier Notary Public.

15-009-19335-00-00

December 6, 1947

Hitschmann Office

John A. Trimmell

Well Log on N. J. Weber "A" # 5

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1971
CONSERVATION DIVISION
Wichita, Kansas

Well started: October 17, 1947
Well completed: November 8, 1947

Elevation
Sec. 11-16-12W
NE-NE-SE Barton Co.

Well Log:

Anhydrite 730 - 80'
Kansas City 3052' Fair show oil
Arbuckle 3329'

T.D.R. 3356'

Casing Record:

8 5/8" Csg. set @ 276' cemented
with 95 sax.

5 1/2" OD 15.5# Smls. Csg. set @ 3330'
cemented with 150 sax.

Cable-tools:

Drilled shoe @ 3330' did not drill to bottom.

2100' fill up in 30 minutes 500' water.

T.D. 3336'

90' Jts. - 2 3/8" EUE 8 Rd Thd 4.70# Smls Tubing 2816' 6"
112 - 3/4" x 25' Jones # 7 Sucker Rods 2800'

State Test:

124 Bbls. - 65% Water