

15-145-21013-0060

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 3 TWP. 23 RGE. 15 NE/W
Location as in quarters or footage from lines:
C S/2 NW SW

Locate Well
correctly on above
Section Platt.

Lease Owner The Roxana Corp.
Lease Name Smith Well No. A-1
Office Address P.O. Box 1162 Great Bend, KS 67530
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed 2-1-83
Application for plugging filed 2-1-83
Plugging commenced 2-1-83
Plugging completed 2-1-83
Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4120

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Bottom Plug: @ 4080' w/50 sacks 50/50 pozmix, 4% gel 3% cc. thru drill pipe
Next Plug: @ 930' w/50 " " " " " " " "
Next Plug: @ 450' w/40 " " " " " " " "
Top Plug: @ 40' solid bridged plug w/10 sacks
10 sacks in Rat Hole
5 sacks cement in water well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
P.O. Box 877 Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of February, 1983

Deborah M. Blaque
Notary Public.

My Commission expires: 4-29-86

CONSERVATION DIVISION
Wichita, Kansas

2-28-83

15-145-21013-0000

DRILLERS' WELL LOG

DATE COMMENCED: January 26, 1983
DATE COMPLETED: February 1, 1983

Roxana Corporation
SMITH A #1
C S/2 NW SW
Sec. 3, T23S, R15W
Pawnee County, Ks.

ELEVATION: 2012 K.B.

0 - 936' Surface Soil, Shale
936 - 959' Anhydrite
959 - 3452' Shale & Lime
3452 - 3456' Shale
3456 - 3481' Lime & Shale
3481 - 3495' Lime
3495 - 3591' Shale
3591 - 4012' Lime & Shale
4012 - 4092' Shale, Sand, Lime
4092 - 4120' Dolomite
4120' RTD

FORMATION DATA

Anhydrite 936'
Heebner 3452'
Toronto 3481'
Douglas 3495'
Br. Lime 3591'
Lansing 3599'
Simpson Shale 4012'
Simpson Sand 4037'
Arbuckle 4092'
RTD 4120'

Surface Pipe: Set 8-5/8", 23#
pipe @420' w/325 sacks 60/40
pozmix, 2% gle 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 4th day of February 1983.

My Comm. Expires:

4-29-86

L. C. ...
Notary Public

RECEIVED
STATE COMMISSION

MAR 1 1983

CONSERVATION DIVISION
Wichita, Kansas