

WELL PLUGGING RECORD

15-145-10094-00-01

Give All Information Completely
 Make Required Affidavit

COUNTY Pawnee SEC. 3 TWP. 23 RGE. 15 E/W
 Location as in quarters or footage from lines:
NW/NW/NW

Lease Owner Woodman & Iannitti Drilling Co.
 Lease Name Fox "C" Well No. #1 OWWO
 Office Address Box 308 - Great Bend, Ks. 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced August 5, 1983
 Plugging completed August 11, 1983
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4030'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	268'	NONE
				5 1/2"	4029'	2657.16'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3500' and five (5) sacks cement.
Shot casing @ 3200', 3000', 2800' and 2700'.
Pulled eighty-three (83) joints 5 1/2" casing.
Sun Oil Well Cementing squeezed well with four (4) sacks hulls, fifteen (15) sacks gel, fifty (50) sacks cement, ten (10) sacks gel, released plug and pumped one hundred (100) sacks 60/40 pozmix cement added gel and 3% calcium chloride.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 16 1983
 CONSERVATION DIVISION
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 12th day of August, 1983

NOTARY PUBLIC - State of Kansas
 MARGARET PROSSER
 My Comm. Exp. 1-16-86

Margaret Prosser
 Notary Public.

My Commission expires: