

15-445-61320-0000

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


COPY

Company. THE ATLANTIC REFINING CO.
Farm. Jay T. Smith No. 2

SEC. 3 T. 23 R. 15W
C NW SW SW

Total Depth. 4090
Comm. 6-4-55 Comp. 6-17-55
Shot or Treated.
Contractor. Lewis Drilling Co.
Issued. 8-27-55

County Pawnee
K/NS'S



CRDING:

8 5/8 @ 410.05' w/ 300 sx cmt.
4 1/2 @ 4088' w/ 200 sx cmt.

Elevation. 2014 DF

Production. 81 BOPD

Figures indicate Bottom of Formations.

sand	250
clay	330
red bed	374
sand & shale	418
sand	670
shale	940
anhydrite	965
shale & shells	1052
red bed	1170
shale & shells	1710
shale & lime	2950
shale	3200
lime & shale	3640
lime	3780
lime & shale	3930
lime & chert	3964
shale & chert	4000
chert, lime & shale	4050
lime & shale	4080
Arbuckle lime	4090
Total Depth	

TOPS:	
Heebner	3456
Toronto	3485
Brown lime	3592
Lansing	3602
Conglomerate	3928
Viola	3961
Simpson shale	4022
Simpson sand	4041
Arbuckle	4080

Perf. 4033-57 (Simpson) w/ 4 JSPF,
On 12 hr tst, prod. 66 BO

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1965

CONSERVATION DIVISION
Wichita, Kansas