


15-145-00186-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

PAWNEE County. Sec. 3 Twp. 23S Rge. 15W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW/4 NW/4 SW/4
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name JAY T. SMITH Well No. 1
Office Address P.O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) IMPUT
Date well completed AUGUST 23 19 54
Application for plugging filed SEPTEMBER 2 19 65
Application for plugging approved SEPTEMBER 3 19 65
Plugging commenced SEPTEMBER 3 19 65
Plugging completed SEPTEMBER 16 19 65
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4088' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	398'	NONE
				5 1/2"	4087'	3010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4088' - 3650' - SAND
3650' - 3610' - 5 SACKS CEMENT
3610' - 600' - MUD
600' - 410' - PUMPED 13 SACKS MUD
410' - 210' - PUMPED 40 SACKS CEMENT
210' - 40' - MUD
40' - 30' - ROCK BRIDGE
30' - BASE - 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address P.O. BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T.L. NUTT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T.L. Nutt*
P.O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of NOVEMBER, 19 65

My commission expires JULY 31, 1966
Mary M. Guenier
Notary Public.

15-145-00186-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- ATLANTIC REFINING CO.
Farm- Jay T. Smith No. 1

SEC. 3 T. 23 R. 15W
C NW NW SW

Total Depth. 4088
Comm 8-11-54 Comp. 8-23-54
Shot or Treated. Perf. 4023-37
Contractor. Lewis Drilling Co.
Issued. 11-13-54

County Pawnee
KANSAS



Elevation. 2009 DF

Production. 196 BOPD

CASING:

8 5/8 @ 398' w/ 300 sx cmt.
5 1/2 @ 4087' w/ 200 sx cmt.

Figures Indicate Bottom of Formations.

cellar	4
sand	120
shale	410
sand	480
shale	510
shale, red bed & sand streaks	650
red bed & sand streaks	945
anhydrite	960
shale & red bed	1335
shale & sand	1750
shale, shells & sand strks.	1835
lime & shale	2465
shale	2650
lime & shale	3605
lime	3815
lime & shale	3913
conglomerate	3925
lime & shale	4069
Arbuckle	4088
Total Depth	

SCOUT TOPS:

Lansing	3588
Viola	3946
Simpson	4012
Simpson sand	4031
Arbuckle	4063

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1965

CONSERVATION DIVISION
Wichita, Kansas