

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

OCT 24 1975

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Et Al, Inc. 15-145-70087-0000

Complete Address 119 Cameran Bldg., Oklahoma City, Oklahoma 73106

Lease Name Thelma Well No. 1

Location SW NW NW Sec. 3 Twp. 23 Rge. (E) (W) 15

County Pawnee Total Depth 3020'

Abandoned Oil Well        Gas Well XX Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 10:30 A Day 23 Month 10 Year 1975

The above well was plugged as follows:

Total Depth 3020' 8 5/8 csg set 249' cwc 200 sk.

4 1/2 csg set 2990' cw 225 sk cem.

Filled 4 1/2 csg W/sd (3020-2800) dumped 4 sk cem W/dump bailer. (2800-2770)

Cutoff & recovered A/1900' of 4 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released 8 5/8 plug & pumped 125 sk 60/40 poz cem. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 10/24/75

INV. NO. 2122-W