

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-145-00186-0000

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply
Complete Address: Box 562 Great Bend, Kan s
Lease Name J. T. Smith Well No. 1
Location CNW SW Sec. 3 Twp. 23 Rge. (E) (W) 15
County Pawnee Total Depth 4088
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: same
Address: same License No. 5 74
Operation Completed: Hour 4PM Day 16 Month 9 Year 65

The Above well was plugged as follows:

598'
8 5/8" 308 circulated with cement - 5 1/2" 4087' with 200 sax cement
per 3088'

Set plug at 5650', sand to 3600', 4 sax cement set with dump bailer.

Pulled 2900' 5 1/2" to 600', circulated hole with heavy gel mud through 5 1/2"
at 600' pulled pipe to 410', displaced 20 sax cement through 5 1/2" at 410'
pulled pipe to 210', displaced 20 sax cement through 5 1/2" at 210', heavy
mud to 55', cement 55' to 0'

Mudding and cementing by Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/28/65
INV. NO. 1883-W

Signed: Edon Peay
Well Plugging Supervisor