

W
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1965
5-19-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mayfield-Smith Drilling, Inc.

Complete Address: 928 Union Center, Wichita, Kansas

Lease Name Du Bois Well No. 1

Location C SE NE Sec. 22 Twp. 21 Rge. 4 (E) (W) X

County Mc Pherson Total Depth 3861'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Operator

Address: License No.

Operation Completed: Hour 12 PM Day 16 Month May Year 1965

The Above well was plugged as follows:

Hole filled with mud to 555'. Plug and 1/4 sack hulls pushed to 555' and
hole cemented with 20 sacks through drill pipe. Hole filled with mud
to 200'. Plug and 1/4 sack hulls pushed to 200' and hole cemented with
20 sacks through drill pipe. Hole filled with mud to 40'. Plug and
1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10
sacks. Rathole bridged, and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *William J. Loman*
Well Plugging Supervisor

DATE 5/19/65

INV. NO. 1196-W