

Form GP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION

DEC 2 1963

CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Donald Slawson Oil Co.Complete Address: 1621 First Nat'l Bldg., Wichita, Kansas.Lease Name Lagree "H" Well No. 1Location C NE N7 Sec. 27 Twp. 21s Rge. 1 (E) (W)County McPherson Total Depth 3517'Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XOther well as hereafter indicated:     Plugging Contractor: Renfro Drilling CompanyAddress: 313 Insurance Bld'g. Wichita, Kansas. License No. RotaryOperation Completed: Hour 2:30AM Day 26 Month 11 Year 63

The Above well was plugged as follows:

Filled hole w/ 36 vis mud from T.D. 3517' back to 190' set a Halco plug 1/2 sak hulls  
and ran 20 sax cement from 180' back to 120'. Filled hole w/ 36 vis mud from 120' back  
to 35' set a halco plug 1/4 sak hulls and ran 8 sax cement from 25' back to zero 4'  
below ground level. 8 5/8" surface pipe 4' below ground level. Filled rat hole w/ mud  
and 2 sax cement 3' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Cecil W. Janner  
Well Plugging SupervisorDATE 12/3/63INV. NO. 8206-W