

1 010025

API NUMBER 15- 185-21,729-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE NW, SEC. 21, T 23 S, R 14 W2E

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Mann Well # 1-21

Operator: Texas Energies, Inc.

County Stafford 133.90

Name & Address P. O. Box 947

Well Total Depth 4120 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:40 pm Day: 27 Month: August Year: 19 85

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4072' PBT 4016' Perfs at 3925-3928'

1st plug sand back to 3875' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 130 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All y Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 27 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3870 and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 130 sx cement.

RECEIVED STATE CORPORATION COMMISSION 9-6-85

SEP 6 1985

Maximum pressure 550 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2730 4 1/2" casing, Kansas

(if additional description is necessary, use BACK of this form.)

INVOLCED

DATE SEP 10 1985

INV. NO. 9965

Signed [Signature] (TECHNICIAN)