

1 080248

API NUMBER 15- 185-21,212 -0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW SE SE, SEC. 21, T 23 S, R 14 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

990 feet from N SE Corner of  
990 feet from W SE Corner of  
XXX section line  
XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050 Lease Name Beaver Well # 1  
(Bought from Reach Group)  
Operator: Kelso Casing Pulling County Stafford  
Name & Address Box 347, Chase, KS 67524  
Well Total Depth 3748 121-81 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 225'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 30 Month: October Year: 19 84

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3793' Perfs at 3691-98'

1st plug sand back to 3640' and dump 4 sx cement on top of sand through bailer.  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by J. H. Metz NOV 08 1984  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_  
None \_\_\_\_\_  
CONSERVATION DIVISION  
Wichita, Kansas

Operations Completed: Hour: 10:15 am Day: 30 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3793' Perfs at 3691-98'

1st plug sanded back to 3640' and dumped 4 sx cement on top of sand through bailer, 2nd plug  
squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released  
8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 400 psi and shut in pressure 100 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc. Recovered 2918' 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

INVOICED

Signed J. A. Metz (TECHNICIAN)

DATE 11-14-84

INV. NO. 4731 10-30