

To: 1 120669
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-8-92 54 R
API NUMBER 15-185-22,421-0000
N/2 SE NW, SEC. 25, T 23 S, R 14 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5097
Operator: Martin Oil Producers, Inc.
Name & Address: 150 N. Main, Suite 1010
Wichita, KS 67202

3630 feet from S section line
3300 feet from E section line
Lease Name Radke Well # 1
County Stafford 132.04
Well Total Depth 4063 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 424

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 8 Month: 1 Year: 1992

Plugging proposal received from William Stockstill
(company name) Martin Oil Producers, Inc. (phone) 316-257-2227

were: 5 1/2" at 4060' w/150 sx cement, Perfs at 3694-98, 3736-42', Open hole 4060-4063'
1st plug sand back to 3650' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 8 Month: 1 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 3650' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1999' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE JAN 29 1992

INV. NO. 34410

Signed [Signature] (TECHNICIAN)

RECEIVED (KANSAS CORPORATION COMMISSION)

JAN 16 1992

CONSERVATION DIVISION WICHITA, KS