

To: 1 030603
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,310 -0000

R

NW NE SW, SEC. 32, T 23 S, R 14 W
2310 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6009

Lease Name Leitner Well # 1

Operator: Double Eagle Exploration, Inc.

County Stafford 132.96

Name &

Address 100 South Main, Suite 410

Well Total Depth 4091 -Arbuckle 4' feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rains & Williamson Oil Co., Inc. License Number 5146

Address 435 Page Court, 220 W. Douglas, Wichita, KS 67202

Company to plug at: Hour: 8:00 am Day: 22 Month: November Year: 19 85

Plugging proposal received from Bill Chance

(company name) Rains & Williamson (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1977
Anhydrite 888'

1st plug in the Arbuckle with 40 sx cement if 50' or more

2nd plug at the base of the Anhydrite with 50 sx cement

3rd plug at 280' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement. Plug water well with 10 sx cement

Plugging Proposal Received by Dan Goodrow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 am Day: 22 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement, 2nd plug at 280' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton # 083892

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed

Steve [Signature]
(TECHNICIAN)

DATE 12-6-85

DEC 5 1985

INV. NO. 11286

CONSERVATION DIVISION

12-5-85

FORM CP-2/3
Rev. 01-84