

To: 1 120617
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202
TECHNICIAN'S PLUGGING REPORT
Operator License # 30606
Operator: Murfin Drilling Company, Inc.
Name & Address 250 N. Water, Suite 300
Wichita, KS 67202

9-9
API NUMBER 15- 185-22,800-0000 28R
NE SE SE, SEC. 23, T 23 S, R 14 W/E
1100 feet from S section line
330 feet from E section line
Lease Name Merrick Well # 3-23
County Stafford 132.92
Well Total Depth 4090 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 396

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor LOBO Drilling Co. License Number 5864

Address P.O. Box 877, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 9 Month: 9 Year: 19 91

Plugging proposal received from Ervin Neighbors

(company name) LOBO Drilling Co. (phone) 316-792-7476

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 850-873'
1st plug at 873' with 50 sx cement,
2nd plug at 420' with 50 sx cement, 3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 9 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 873' with 50 sx cement,
2nd plug at 420' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

(if possible) observe this plugging.

DATE 10-7-91
INV. NO. 33287

Signed Dean Parker
(TECHNICIAN)

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

State of Kansas

NOTICE OF INTENTION TO DRILL

185-22,800-0500

Must be approved by the K.C.C. five (5) days prior to commencing well

EFFECTIVE DATE: 9-4-91
DISTRICT: 2
SEAT: X

Expected Spud Date: 9-3-91
month day year

Spot: NE-SE-SE Sec. 23, Twp 23, S. Rg 14, East West

OPERATOR: License # 30606
Name: Murfin Drilling Company, Inc.
Address: 250 N. Water, Suite 300
City/State/Zip: Wichita, KS, 67202
Contact Person: Scott Robinson
Phone: 316-267-3241

1100 feet from South ~~West~~ line of Section
330 feet from East ~~West~~ line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stafford

Lease Name: MERRICK Well #: 3-23
Field Name: New Pool - Not named yet

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): KGC/Arbuckle

Nearest lease or unit boundary: 330
Ground Surface Elevation: FGL 1940 feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 240'

Surface Pipe by Alternate: XX 1 2
Length of Surface Pipe Planned to be set: 300'

Length of Conductor pipe required: N/A
Projected Total Depth: 4100'

Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:

X well farm pond other
DWR Permit #: 90-0481

Will Cores Be Taken? yes X no
If yes, proposed zone:

260' Alt. I Req.

CONTRACTOR: License #: 30606
Name: Murfin Drilling Company, Inc.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OUVO ... Disposal X Wildcat ... Cable
... Seismic; ... # of Holes ... Other

If OUVO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 2/29/92.

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101 et seq.

Pusher: Invin
SPUD DATE: 9-3-91 INIT. CA
LENGTH SURFACE PLANNED: 300'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/8 @ 396' CONDUCTOR
ANHYDRITE T- 830 B- 873 ELEVATION

TD 4090' FORMATION Arbuckle

RAN PIPE @ DV TOOL ALT II DONE
SX Y N SX Y N
Arbuckle Plug @ if need Ft. W/ 40 SX

Hug / Council @ Ft. W/ SX
Anhydrite Base @ 873 Ft. W/ 50 SX

Base Anyh. @ Ft. W/ SX
1/2 Plug @ Ft. W/ SX
Bottom Surface @ 420 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN SP DATE 9-5-91
TYPE OF CEMENT Gel/90 per 6' gel

STARTING TIME 1:30 (AM/PM) DATE 9-90-91

COMPLETION TIME 4:00 (AM/PM) DATE 9-9-91

CEMENT COMPANY A 11/100 60/40 60z

RECEIVED
STATE CORPORATION COMMISSION
SEP 16 1991
CONSERVATION DIVISION
Wichita, Kansas

Phone: 316-267-3241