

DEC 3 1 1986
API NUMBER 15- 15-009-22800-00-00

SW, SEC. 10, T. 16 S, R. 12 W/E
2310 feet from S section line
2970 feet from E section line

Lease Name Reiman Well # 1
County Barton 108.71
Well Total Depth 3345 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 250

To: 6 061165
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Operator: Mustang Companies, Inc.
Name & Address: Box 91609
Great Bend, Mo.
67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, Mo. 67524

Company to plug at: Hour: 11:00AM Day: 31 Month: Dec. Year: 1986

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: Order 100 sl. 6 5/8" permix - 10% Gel. - 2% Econlit, 5 sl. hull

Plugging Proposal Received by John G. Shul
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30PM Day: 31 Month: Dec. Year: 1986

ACTUAL PLUGGING REPORT 8 5/8" - 250' c/c. 5 1/2" - 3338' w/100 sl. Top perf - 3134'

Plugged bottom w/ sand & 5 sh. cement to 3075', shot pipe 2 times & recovered 2000'. Pumped in 8 5/8" - 5 sh. hulls, 100 sh. cement w/ 800 p.s.i.

STATE CORPORATION COMMISSION
1-7-87
JAN 7 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: By Allied
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-7-87

INV. NO. 15841

Signed John G. Shul
(TECHNICIAN)