

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145 21,013-0000 ✓

SW 1/4, Sec. 3, T 23 S, R 15 W 1/4

3630 feet from N 1/4 section line

660 feet from W 1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6283

Lease Name SMITH Well # A#1

Operator: THE ROXANA CORPORATION

County PAWNEE

Name & Address Box 1162
GREAT BEND, KS 67530

Well Total Depth 4120 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor LOBO DRILLING CO. License Number 5864

Address Box 877, GREAT BEND, KS 67530

Company to plug at: Hour: 6:00 AM Day: 1 Month: FEB Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Irvin Neighbors

(company name) Lobo (phone) _____

were: use 50/50 Pozmix, 4% gel. - 3% C.C. - locate 1st plug @ 4080' w/50 sy; 2nd plug @ 930' w/50 sy; 3rd plug @ 450' w/40 sy; 4th plug @ 40' w/solid bridge of hulls & wiper plug, then cement to surface w/10 sy, circ. 10 sy in radial & 5 sy in water well.

Signed R. Barlittan (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:30 pm Day: 1 Month: 2 Year: 19 83

ACTUAL PLUGGING REPORT plugged as ordered.
Cementing by Sun Oilwell Cementing.

Remarks: anhydrite top 936' - ar buckle top 4085

RECEIVED STATE CORPORATION COMMISSION

FEB 10 1983

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 3-10-83
INV. NO. 3559-W

Signed R. Barlittan (TECHNICIAN)