

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-20955-00-00

Spot: E/2SWNE

Sec/Twnshp/Rge: 17-21S-4E

3135 feet from S Section Line, 1485 feet from E Section Line

Lease/Unit Name: BROWN

Well Number: 8

County: MARION

Total Vertical Depth: 2442 feet

Operator License No.: 3639

Conductor Pipe: Size

feet:

Operator Name: LONGHORN OIL & GAS

Surface Casing: Size 8.625

feet: 207

Address: 1249 NW 40TH  
EL DORADO, KS 67042

Production: Size 5.5

feet: 2484

Liner: Size

feet:

79.37

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 9/15/00 12:00:00 PM

Plug Co. License No.: 32475

Plug Co. Name: BRADEN PETROLEUM & WELL PLUGGING COMPANY

Proposal Rcvd. from: FRED STACKLEY

Company: LONGHORN OIL & GAS

Phone: (316) 321-5136

Proposed Plugging Method: PERFORATIONS FROM 2,080' TO 2,083'. SAND TO 2,030' AND TOP WITH 5 SXS. CEMENT. SHOOT PIPE OFF. PULL PIPE TO 260' AND CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: MICHAEL WILSON

WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 09/15/2000 1:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,030' AND TOPPED WITH 5 SXS. CEMENT. SHOT PIPE OFF AT 1,310' AND PULLED TO THE SURFACE. RAN 2 3/8" TUBING TO 280' AND CIRCULATED 110 SXS. CEMENT TO THE SURFACE.

RECEIVED  
KCC DISTRICT #2

SEP 23 2000

WICHITA, KS

Remarks: USE D60/40 POSMIX W/4% GEL BY UNITED. INVOICE #2195. RETRIVED 1,310' (31 JTS.) OF CASING.

Plugged through: TBG

District: 02

Signed

Michael Wilson

(TECHNICIAN)

INVOICED

DATE

9/25/00

INV. NO.

2001060727