

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21251-00-00
Spot: SENE SWNE Sec/Twnshp/Rge: 17-21S-4E
3440 feet from S Section Line, 1380 feet from E Section Line
Lease/Unit Name: BROWN Well Number: 9
County: MARION Total Vertical Depth: 2145 feet

Operator License No.: 3639
Operator Name: LONGHORN OIL & GAS
Address: 1249 NW 40TH
EL DORADO, KS 67042

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 210
Production: Size 4.5 feet: 2138
Liner: Size feet: 69.71

Well Type: EOR UIC Docket No: E-26,690 Date/Time to Plug: 9/15/00 9:30:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN PETROLEUM & WELL PLUGGING COMPANY
Proposal Rcvd. from: FRED STACKLEY Company: LONGHORN OIL & GAS Phone: (316) 321-5136

Proposed Plugging Method: PERFORATIONS FROM 2,087' TO 2,090'. SAND TO 2,037' AND TOP WITH 4 SXS. CEMENT. SHOOT PIPE OFF. PULL PIPE TO 260' AND CIRCULATE CEMENT TO THE SURFACE.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 09/15/2000 11:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

SANDED TO 2,035' AND TOPPED WITH 4 SXS. CEMENT. SHOT PIPE OFF AT 1,620' AND PULLED TO THE SURFACE. RAN 2 3/8" TUBING TO 280' AND CIRCULATED 110 SXS. CEMENT TO THE SURFACE.

RECEIVED
KCC DISTRICT #2

SEP 23 2000

WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL GEL BY UNITED. INVOICE #2195. RETRIVED 1,620' (42 JTS.) OF CASING.

Plugged through: TBG

District: 02

Signed

Michael R. Wilson
(TECHNICIAN)

INVOICED
DATE 9/25/00
INV. NO. 2001060727