



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

RECEIVED  
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

JUL 1 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Jim Lahar of Glickman Oil Company has this

date requested permission to plug the following described well:

Mr. J. M. Glickman guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Comapny

Complete Address: Box 3104, Wichita, Kansas

Lease Name: Schauf Well No. # 1

Location: NE NE NW Sec. 11 Twp. 16 Rge. 12 (E) (W)

County Barton Total Depth 3371 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Jim Lahar was instructed to plug the well as follows:

10 3/4" 270' Cwc.

Filled hole with heavy mud to 260'; set plug with 1/2  
sax hulls, & displaced 30 sax cement thru drill pipe. Mud  
to 30', 1/2 sax hulls, plug, & displaced 15 sax cement,  
cementing to base of cellar.

Very truly yours,

Don Truman  
 Conservation Division Agent