

State of Kansas



15-009-20322-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Johnnie Crowe of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Petroleum, Inc. guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name: Schauf "B" Well No. # 2

Location: SE NW SW Sec. 11 Twp. 16 Rge. 12 (E)(W) W

County: Barton Total Depth 3400 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnnie Crowe was instructed to plug the well as follows:

8 5/8" 286' Cwc.

Circulated hole with heavy mud to 500', set plug with 1/4 sax hulls,

& displaced 40 sax cement thru drill pipe. Mud to 280', displaced 25

sax cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & dis-

placed 10 sax cement with Globe Cementing Company's pump truck, cementing

to base of cellar. STATE CORPORATION COMMISSION

Very truly yours,

DEC 10 1968

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent