



15-113-30026-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 19 1965
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Geo. Calloway of Mayfield-Smith Drlg., Indas this date requested permission to plug the following described well:

Mr. Calloway guarantees payment of the plugging fee.

Operator's full Name: Mayfield-Smith Drilling, Inc.

Complete Address: 928 Union Center, Wichita, Kansas

Lease Name: Du Bois Well No. 1

Location: C SE NE Sec. 22 Twp. 21 Rge. 4 (X) (W) X

County Mc Pherson Total Depth 3861' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Calloway was instructed to plug the well as follows:

Fill hole with mud to 555'. Push plug and 1/2 sack hulls to 555' and cement hole with 20 sacks. Fill hole with mud to 200'. Push plug and 1/2 sack hulls to 200' and cement hole with 20 sacks. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Arthur J. Loman
Conservation Division Agent