

State of Kansas



FORM - CP-2
Rev. 6-26-62

15-113-00562-0000

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 2 1963
12-2-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Dean Glover of Renfro Drilling Co. has this
date requested permission to plug the following described well:

Mr. Glover guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson Oil Co.

Complete Address: 621 First Nat'l Bldg. Wichita, Kansas.

Lease Name: Lagree "H" Well No. 1

Location: C NE NW Sec. 27 Twp. 21s Rge. 1 (E)/(W)

County McPherson Total Depth 3517' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glover was instructed to plug the well as follows:

Fill hole w/ 36 Vis mud from T.D. 3517' back to 190' set a plug and
run 20 sax cement. Fill hole w/ 36 vis mud^{Back to 30'} set a bridge and run 8
sax cement back to zero 4' below ground level. Fill rat hole w/ mud
and 2 sax cement back to zero 3' below ground level.

Very truly yours,

Conservation Division Agent