

15-185-00736-0000

## WELL PLUGGING RECORD

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Stafford County, Sec. 23 Twp. 23 Rge. (E) 14 (W)  
Location as "NE/CNW¼SW¼" or footage from lines NE SE NW  
Lease Owner Jackson Drilling Corporation  
Lease Name Miller Well No. 1  
Office Address 1009 Central Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed December 20, 1951 19  
Application for plugging filed (Orally) December 21, 1951 19  
Application for plugging approved December 27, 1951 (written) 19  
Plugging commenced December 22, 1951 19  
Plugging completed December 22, 1951 19  
Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production.....19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough

Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... 4045 DF Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

Filled hole with heavy mud from total depth to 250 feet

Set plug at 250 feet and ran 15 sacks cement to 210 feet

Filled with heavy mud from 210 feet to 30 feet

Set plug at 30 feet and ran 10 sacks cement to cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....Westgate-Greenland Oil Company  
Address 1009 Central Building Wichita 2, Kas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

G. E. Bitler (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature).

1009 Central Building, Wichita 2, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 29th day of December 19 51

My commission expires May 25, 1953.

23-3278-S

4-50-10M

PLUGGING  
FILE SEC 23 T 23 P14W  
BOOK PAGE 131 LINE 28

15-185-00736-0000

COMPANY: Jackson Drilling Corporation  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Miller No. 1  
 LOCATION: NE SE NW Section 23-23-14W,  
 Stafford County, Kansas  
 COMMENCED: December 6, 1951  
 COMPLETED: December 20, 1951  
 ELEVATION: 1927 DF

|      |    |      |                          |
|------|----|------|--------------------------|
| 0    | to | 50   | Soil and sand            |
| 50   | to | 80   | Sand W/shale             |
| 80   | to | 295  | Shale                    |
| 295  | to | 360  | Sand                     |
| 360  | to | 833  | Red bed W/shale and sand |
| 833  | to | 857  | Anhydrite                |
| 857  | to | 1250 | Shale and shells         |
| 1250 | to | 1265 | Shale and shells W/salt  |
| 1265 | to | 1300 | Shale W/salt             |
| 1300 | to | 1645 | Shale and shells         |
| 1645 | to | 1875 | Shale W/lime             |
| 1875 | to | 1990 | Lime W/shale breaks      |
| 1990 | to | 2970 | Shale and lime           |
| 2970 | to | 2980 | Lime                     |
| 2980 | to | 3510 | Shale and lime           |
| 3510 | to | 3530 | Shale                    |
| 3530 | to | 3543 | Brown lime               |
| 3543 | to | 3782 | Lansing lime             |
| 3782 | to | 3823 | Shale and lime           |
| 3823 | to | 3866 | Shaley Conglomerate      |
| 3866 | to | 3887 | Cherty Conglomerate      |
| 3887 | to | 3889 | Chert                    |
| 3889 | to | 3917 | Cherty lime              |
| 3917 | to | 3937 | Lime, chert and shale    |
| 3937 | to | 3946 | Chert and lime           |
| 3946 | to | 3985 | Shale-lime and sand      |
| 3985 | to | 4000 | Lime-shale and chert     |
| 4000 | to | 4035 | Shale and sand           |
| 4035 | to | 4047 | Arbuckle                 |
|      |    | 4047 | T. D. Rotary (RB)        |

Set 260 feet of 8 5/8" 24# surface pipe. Cemented with 200 sacks cement and 2 sacks calcium chloride.

Drill Stem Tests: 3608-38, open 45 min, rec 75' muddy salt water, 1200# BHP.  
 3675-3716, open 1 hour, rec 310' slightly oil and gas cut mud, no BHP.  
 3726-80, open 1 hour, rec. 2400' salt water, 1270# BHP.

TOPS: Heebner 3391. Brown Lime 3528. Lansing 3541. B/KC 3796.  
 Conglomerate 3869. Viola 3894. Simpson 3975. Arbuckle 4027.

Ran Schlumberger.

Dry, plugged and abandoned.

PLUGGING

FILE SEC 23 T 23 R 14 W

BOOK PAGE 133 LINE 28

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of log of the Miller No. 1 well, Section 23-23-14W, Stafford County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Harold A. Burt  
Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas this ~~21st~~ 29th Day of December, 1951.

Esther Unsell  
Notary Public

My commission expires May 25, 1953.

DEC 31 1951  
STAFFORD COUNTY, KANSAS