

15-009-03273-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barton

County, Sec. 10 Twp. 16S Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines C S/2 NE SW

Lease Owner National Cooperative Refinery Association

Lease Name Christians Well No. 3

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 21, 1950

Application for plugging filed April 18, 1957

Application for plugging approved April 19, 1957

Plugging commenced April 25, 1957

Plugging completed May 6, 1957

Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production October 30, 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation Arbuckle Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3322.5 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	472'	None-Cemented
				5 1/2"	3318 1/2'	2710.49

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Knocked bridge out at 1300'. Sanded hole to 3300'. Dumped 5 sacks of cement. Pulled 5 1/2" casing. Mudded hole to 320', set rock bridge, dumped 20 sacks of cement. Mudded hole to 20', set rock bridge plus 5 sacks cement on up to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 16 1957

CONSERVATION DIVISION

5-16-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R and D Casing Pulling Company

Address Box 569, Ellinwood, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss. C. R. Sears (employee of owner) or John H. Sears of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1957

Nell McComb

My commission expires November 26, 1960.

Nell McComb Notary Public.

PLUGGING  
FILE SEC 10 T 16 R 12W  
BOOK PAGE 7 LINE 21

THE NATIONAL COOPERATIVE REFINERY ASSOCIATION

#3 Christians, C S/2 NE SW 10-16-12  
Barton County, Kansas

COMMENCED: 4-29-50  
COMPLETED: 5-11-50

0	55	Lime
55	100	Shale and shells
100	240	Shale and shells
240	410	Shale, sand and shells
410	474	Lime, shale, sand, iron
474	505	Shale and shells
505	790	Red bed and shells
790	800	Anhydrite
800	820	Anhydrite
820	1060	Shale and shells
1060	1310	Shale and shells
1310	1460	Shale, shells and salt
1460	1530	Lime and shale
1530	1695	Shale and broken lime
1695	1760	Shale and shells
1760	1880	Lime broken
1880	1995	Lime
1995	2110	Shale and lime
2110	2250	Lime and shale
2250	2405	Lime and shale
2405	2535	Shale and lime
2535	2690	Shale and shells
2690	2750	Shale and lime
2750	2790	Lime
2790	2845	Lime
2845	2940	Lime and shale
2940	3040	Shale and lime
3040	3052	Lime and shale
3052	3085	Lime
3085	3135	Lime
3135	3165	Lime
3165	3229	Lime
3229	3253	Lime
3253	3315	Lime
3315	3326	Lime
3326		Rotary Total Depth

Gasing Record  
Set 8-5/8" surface casing at 474' with 225 sacks  
  
Set 5-1/2" casing at 332 1/2' with 75 sacks

STATE OF KANSAS )  
 ) SS  
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #3 Christians located C S/2 NE SW 10-16-12, Barton Co., Kansas.

RECEIVED  
NOTARY COMMISSION

ANSCHUTZ DRILLING COMPANY, INC.

APR 19 1950

By: *H. R. Jensen*

Subscribed and sworn to before me this 18th day of May, 1950.

*Martha Jones*  
Notary Public

My commission expires September 12, 1953

PLUGGING  
FILE SEC. 10 T. 16 R. 12W  
BOOK PAGE 7 LINE 21

RECEIVED  
R. E. W. A.  
MAY 19 1950