

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barton County. Sec. 10 Twp. 16 Rge. 12 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NW SW

Lease Owner Bennett & Roberts Drilling Co.

Lease Name Christians Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 2/27 19 54

Application for plugging filed 2/26 verbally 19 54

Application for plugging approved 2/26 verbally 19 54

Plugging commenced 2/27 19 54

Plugging completed 2/27 19 54

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3368 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	473'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'. Dumped 1/3 sack hulls, pushed HowCo. plug to 300'. Cemented w/20 sx thru drill pipe. Filled to 35' with heavy mud. Dumped 1/3 sack hulls. Pushed HowCo. plug to 35'. Cemented w/10 sx.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor None

Address

STATE OF KANSAS COUNTY OF RUSSELL, ss.
C. L. Roberts (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BENNETT & ROBERTS DRILLING CO.

(Signature) [Signature]

Russell, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 54

[Signature] Notary Public.

My commission expires 6/17/54

PLUGGING
FILE SEC 10 T 16 R 12
BACK PAGE 10 LINE 65

3-3-54
CONSERVATION DIVISION
Wichita, Kansas

Bennett & Roberts Drilling Co.
Christians #1

SE NW SW Sec. 10-16-12
Barton County, Kansas

R.T.D. 3368'

Comm: 2/16/54
Comp: 2/27/54

8 5/8 @ 473' w/250 sx cmt.

Formation:	Depth:
Surface Clay & Post Rock	40'
Sandy Post rock & Shale Stks	60
Blue Shale	140
Shale Stks pyrite	210
Shale & Shells	335
Shale & Sand	380
Shale	395
Sand	430
Shale	440
Hard Sand	455
Shale	500
Red Bed	800
Anhydrite	825
Red Bed, Shale & Shells	975
Shale	1300
Shale & Shells	1445
Salt & Shale	1480
Shale & Lime	1780
Lime	2010
Shale & Lime	2934
Lime	3317
Conglomerate	3340
Sand	3368

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct
to the best of my knowledge.

John Lake

Subscribed and sworn to before me this 2nd of March, 1954.

Clara L. Sumner
Notary Public

My Commission Expires 6/17/54

PLUGGING
FILE SEC 10 T 16 R 20
BOOK PAGE 16 LINE 45

CONCORD