

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Barton County. Sec. 10 Twp. 16 Rge. 12 (E) W (W)
 Location as "NE/CNW/SW" or footage from lines SE NW C E 1/2
 Lease Owner SPECTER PIPE & SUPPLY, INC.
 Lease Name N.J. WEBER Well No. B# 5
 Office Address Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) oil
 Date well completed 5-26-50 19__
 Application for plugging filed Oct. 11, 1969 19__
 Application for plugging approved Oct. 13, 1969 19__
 Plugging commenced DECEMBER, 17, 1969 19__
 Plugging completed DECEMBER, 23, 1969 19__
 Reason for abandonment of well or producing formation failure to produce profitably
 If a producing well is abandoned, date of last production _____ 19__
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN
 Producing formation Arbuckle Depth to top 3317 Bottom 3318 Total Depth of Well 3322 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	500 ft.	none
				5 1/2" OD	3318 ft.	2620 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged, back with sand to 3000- feet, dumped 5- sacks Cement.
Pumped ten sacks Mud, & 100- Sacks Cement.

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 5 1969
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor LYNCH CASING PULLING, COMPANY. NO. 457
 Address R.R. 4 GREAT BEND, KANSAS. 67530

STATE OF Kansas, COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 31st day of December, 1969

My commission expires May 21, 1971
Milona M. Lindahl Notary Public.

15-009-15722-00-00
 WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY,
 508 E. Murdock Wichita, Kansas


COPY

Company - NATIONAL COOPERATIVE REFINERY ASSOC.
 Farm - Wober "B" No. 5

SEC. 10 T. 16 R. 12W
 C E $\frac{1}{2}$ SE NW

Total Depth. 3322
 Comm. 5-12-50 Comp. 5-26-50
 Shot or Treated.
 Contractor. Anschutz Drfg. Co., Inc.
 Issued. 7-15-50

County. Barton
 KANSAS



CASING:
 8 5/8" 500' com.
 5 1/2" 3318' com.

Elevation. _____

Production. 174 bbls. oil

Figures Indicate Bottom of Formations.

clay & post rock	50
shale & shells	125
shale, shells, sand	290
sand	320
shale & shells	324
shale, shells, sand	370
shale & shells	420
pyrite, sand & shale	445
shale & shells	485
redbed	500
redbed, shale	640
redrock & shells	810
anhydrite	840
shale & shells	1230
salt, shale & shells	1300
shale & shells	1480
limo	1540
shale & limo	1755
shale, broken limo	1830
limo	1865
shale & shells	1875
limo	1915
shale & limo	2445
shale & shells	2745
limo	2925
limo & shale	3035
limo	3055
shale & limo	3060
limo	3106
shale & limo	3140
limo	3300
limo & shale	3322
Total depth	

S cout Tops:	
Anhydrite	810
Lensing	3048
Arbuoklo	3317

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 13 1969
 CONSERVATION DIVISION
 Wichita, Kansas