

15-009-22801-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barton SEC. 10 TWP. 16 RGE. 12 E/W  
 Location as in quarters or footage from lines:  
 SW SW NW


Lease Owner American Energies Corp.  
 Lease Name REDETZKE Well No. #1  
 Office Address 575 Fourth Financial Center Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed 6-24-82  
 Application for plugging filed 6-24-82  
 Plugging commenced 6-24-82  
 Plugging completed 6-24-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3321'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Bottom Plug: @ 740' w/60 sacks 50/50 pozmix 4% gel 3% cc: thru drill pipe

Middle Plug: @ 240' w/40 " " " " " " " "

Top Plug: @ 40' w/solid bridge of 1/2 sack hulls & 10 sacks cement  
 10 sacks cement in Rat Hole

*Rec'd  
 6-30-82*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (Employee of owner) or ~~(owner or operator)~~ of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Bill Draney  
Box 823 Great Bend, KS 67530  
 (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of June, 1982

Dorothy M. Hague  
 Notary Public.

My Commission expires: 4-29-86

15-009-22801-00-00

Sun Oilwell Cementing  
A Division of BJ Hughes, Inc.

P. O. Box 169  
GREAT BEND, KANSAS 67530

CEMENTING TICKET No. 11872  
and Invoice Number

Date 6-24-82	Customer Order No.	Sp. 10	Twp. 16	Range 17	Truck Called Out 8:00AM	On Location 10:00AM	Job Began 10:45AM	Job Completed 12:15PM
Owner American Energy		Contractor Duke #2			Charge To American Energy			
Mailing Address		City			State			
Well No. and Farm Redetake #1		Place Beave 2N 1E 1/4N E/S			County Barton		State Ks.	
Depth of Well 3321	Depth of Job 740'	Casing New <input type="checkbox"/> Used <input type="checkbox"/>		Size of Hole 7 7/8	Amt. and Kind 120sx	Cement Left in casing by	Request Necessity	
Kind of Job Plug to Abandon				Drillpipe 4 1/2	Rotary Cable		Truck No. #31	
Condition of Well at time of Cementing D.A.				Type of Plugs <del>Drill</del>				

Pressure Circulating \_\_\_\_\_ Minimum \_\_\_\_\_ Maximum \_\_\_\_\_  
 Time Required Mixing Cement \_\_\_\_\_ min. Making Change \_\_\_\_\_ min. Pumping Cement \_\_\_\_\_ min.

Remarks Mixed 120sx 50/50 Poz. 4% Gel. 3% Cal

Price Reference No. #9
Price of Job 37000
Second Stage
Standby Truck
Other Charges
Pump Truck Mileage 4500

60 sx at 740'  
 40 sx at 240'  
 10sx at 40'  
 10sx in Rat Hole

Thanks

Cementor Barry Dale  
 Helper Dale  
 Material Left on Location None  
 District G. Bend State Ks.  
 The above job was done under supervision of the owner, operator, or his agent whose signature appears below

Prices Subject to Correction. State Plugger On Loc. *X L. D. Fiedler*  
 Agent of Contractor or Operator

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
60	5x Common	4.80	
60	5x Poz	1.90	
Cc Cl.	302#	.21	
AM. Cl.	403#	6.10 cwt	
Col			
Plugs			
Delivered by Truck No. T-34		100 Handling and Dumping	.92
Delivered From G. Bend		Mileage 30	.68
Signature of Operator Karl		Sales Tax	.03
		Total Charges	

15-009-22801-00-00

DRILLERS' WELL LOG

DATE COMMENCED: June 17, 1982  
DATE COMPLETED: June 24, 1982

American Energies Corp.  
REDETZKE #1  
SW SW NW  
Sec. 10, T16S, R12W  
Barton County, Ks.

ELEVATION: 1869 K.B.

0 - 770'	Surface Soil, Post Rock, Shale
770 - 793'	Anhydrite
793 - 2758'	Shale & Lime
2758 - 2938'	Lime
2938 - 2961'	Shale
2961 - 2969'	Lime
2969 - 3026'	Shale
3026 - 3037'	Lime & Shale
3037 - 3288'	Lime
3288 - 3305'	Shale, Lime, Chert, Sand
3305 - 3321'	Sand
3321'	RTD

FORMATION DATA

Anhydrite	770'
Topeka	2758'
Heebner	2938'
Toronto	2961'
Douglas	2969'
Br. Lime	3026'
Lansing K.C.	3037'
Base K.C.	3280'
Conglomerate	3288'
Gorham Sand	3305'
RTD	3321'

Surface Pipe: Set new 8-5/8",  
20# pipe @250' w/150 sacks  
60/40 pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 28 day of June 1982.

My Comm. Expires:

4-29-86

Harold M. Hogue  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1982  
CONSERVATION DIVISION  
Wichita, Kansas