


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines: BARTON County. Sec. 11 Twp. 16S Rge. 12 (X) (W)
Lease Owner: PETROLEUM, INC.,
Lease Name: SCHAUF Well No. 2
Office Address: R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole): DRY HOLE
Date well completed: NOVEMBER 28 19 68
Application for plugging filed: NOVEMBER 28 19 68
Application for plugging approved: NOVEMBER 28 19 68
Plugging commenced: NOVEMBER 28 19 68
Plugging completed: NOVEMBER 28 19 68
Reason for abandonment of well or producing formation: NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production: NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well: DONALD TRUAN
Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 3377 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

HEAVY MUD TO 500', FOLLOWED BY WOODEN PLUG, 40 SACKS CEMENT ON TOP OF PLUG.
HEAVY MUD TO 280', FOLLOWED WITH 25 SACKS CEMENT. HEAVY MUD TO 40' ROCK
BRIDGE, WOODEN PLUG, PLACED 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL
CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: GARVEY DRILLING COMPANY
Address: R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner/operating) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.
(Signature) Monte Chadd
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 16 day of DECEMBER, 1968
Richard H. Dumbler
Notary Public.
My commission expires MAY 28, 1969

15-009-20314-00-00
WELL LOG

COMPANY Petroleum, Inc.

SEC. 11 T. 16S R. 12W

FARM Schauf NO. 2


LOC. NE SW NW

TOTAL DEPTH 3377'

COUNTY Barton Co., Kansas

COMM. 11-22-68 COMP. 11-28-68

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 285' w/190 sx

ELEVATION 1898' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

285'	Post Rock
392'	Shale & Sand
426'	Pyrite
785'	Shale & Shells
808'	Anhydrite
1130'	Shale & Shells
1460'	Shale
3000'	Shale & Lime
3377'	Lime
3377'	RTD

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1968
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Eunice McEachern of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Schauf No. 2 well.

Eunice McEachern

Subscribed and sworn to before me this 13th day of December 19 68

My Commission Expires: November 5th, 1969

Richard Hoys
NOTARY PUBLIC