

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-009-00285-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co.

Complete Address P.O. Box 287, Great Bend, Ks. 67530

Lease Name Christian Well No. D-1

Location SW-NE-SE Sec. 10 Twp. 16 Rge. 12 (East) (West)

County Barton Total Depth 3341'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. \_\_\_\_\_

Operation Completed: Hour: 11:50 AM Day: 11 Month: 8 Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 408' S.P. w/ common cement. 5 1/2" set at 3314' w/ 100 sacks common.  
Plugged back to 3080'. Top perf at 2724'. Plugged bottom w/ 75 sacks 50 permix-4 3/4" gel-3 3/4" ball.  
to 2650'. Shot pipe & time & recovered 1600'. Ordered 150 sacks 50 permix-4 3/4" gel-3 3/4" ball,  
5 sacks balls, 15 sacks gel, & 8 5/8" plug. Pumped into S.P., 4 sacks balls, 12 sacks gel, 75 sacks  
cement, 3 sacks gel, 1 sack balls, released plug & followed w/ 75 sacks cement.

Maximum pressure 650 pounds.

Amount of Surface Casing: 408' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Gilbert L. White  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

*(Large handwritten X mark)*

RECEIVED  
AUG 23 1982  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_  
Conservation Division Agent

**INVOICED**

DATE 8-30-82  
INV. NO. 958W